



Residential Air Pressure Test Checklist

1. We require a two 110/240v Electric sockets provided by site.
2. Ensure the Building Envelope is complete. All glazing, external doors and cladding to be complete.
3. Light fixtures to be fitted.
4. All sockets to be fitted.
5. Any penetration made through the external envelope to be sealed.
6. Any loft / storage doors, hatches, to be finished and in place with a draft excluder.
7. SVP and any waste pipes passing through the external walls and ceilings to be sealed.
8. If applicable, all boxing if housing a soil pipe, to be sealed if exiting through the ceiling or external wall.
9. Plumbing installed and all traps to have water in.
10. Skirting boards to be in fixed and sealed top and bottom.
11. Integral garage with internal doors to the house to have draft excluder.
12. If you have a chimney, please make sure this has already been sealed prior to our visit, and any other obvious holes, we seal extractor fans and trickle vents.